



Turner Construction Company
2001 N. Lamar, Suite 100
Dallas, TX 75202
Phone: (214) 721-8400
Fax: (214) 721-8493

9/29/10

Mr. Bill Burke
Collin County
4600 Community Ave.
McKinney, TX 75071

RE: **Collin County Courthouse Addition**
Owner Project #R0508003.00
Turner Project #1692600

SUBJ: PCO #026 – Rerouting 8-Inch Sanitary Sewer Line per RFI 61

Dear Mr. Burke:

We have finalized the required quotations for PC-026 for Rerouting the 8-inch sanitary sewer line to the west of the new building per RFI 61.

We have reviewed the scope of work and have verified that all extra work items are in compliance with our contract agreement. Attached is a detailed itemization of the extra costs. Total amount of this request is **Six Thousand One Hundred and Fifty-Three dollars (\$6,153)**. Please note that this price is good through 3:30 PM on Friday, October 1, 2010. After that time, the utility subcontractor will be substantially complete with all of the work he can do and the costs will have to be re-evaluated.

If you have any questions regarding this Change Order Request, please call me at your earliest convenience.

Please review and acknowledge your approval in the space below. Once approval is achieved, we will expect this PCO to be included in a forthcoming Change Order.

Best Regards,


John Leos

SR

John Leos

Approved by:

Collin County


PGAL

Date

9.30.10
Date

cc: Brad Harris & Sara Hoglund- Collin County
Brian Nicodemus- PGAL
Matt Nail, Suhel Rahman, & Ronnie Holcomb- TCCo



9/29/2010

PCO No.: 026

PCO Title: RFI 61 - Rerouting 8-Inch Sanitary Sewer on the West Side of the New Addition

Project: Collin County Courthouse Addition

Project No.: R0508003.00

Type	Company	Description	Base Price	Subcontractor W/C & GL	Subcontractor Cost
			A	B	C = A+B
Subcontractor	PCI	8" SDR-35, PVC Sewer	2,722	93	2,815
Subcontractor	PCI	Extra vertical depth 8" sewer	(1,513)	(52)	(1,564)
Subcontractor	PCI	Extra vertical depth for 4' dia manhole	(1,188)	(41)	(1,229)
Subcontractor	PCI	4' dia manhole	(2,608)	(89)	(2,697)
Subcontractor	PCI	5' dia standard manhole	4,318	147	4,465
Subcontractor	PCI	5' dia internal drop manhole	4,364	149	4,513
Subcontractor	PCI	Concrete encase 8" sewer	2,000	68	2,068
Subcontractor	PCI	Remove & replace paving	(3,230)	(110)	(3,340)
Subcontractor	PCI	Traffic control	(263)	(9)	(272)
Subcontractor	PCI	Trench safety	52	2	53
Subcontractor	PCI	Layout from controls provided by Turner	175	6	181
Subcontractor	Hudson	Establish Layout and Controls	600	-	600
-			-	-	-
-			-	-	-
-			-	-	-
-			-	-	-
-			-	-	-
-			-	-	-
-			-	-	-
-			-	-	-
-			-	-	-
Subtotal:			5,429	165	5,593

10% OH&P 559
Total Cost \$ 6,153

Notes:

We reserve the right to submit costs for extended general conditions that are a result of this change.

This price is good through 3:30 PM on Friday, October 1, 2010. After that time, the utility subcontractor will be substantially complete with all of the work he can do and the costs will have to be re-evaluated