

GT CONSTRUCTION, INC.

15323 CR 614
Farmersville, TX 75442
(972) 984-7932

April

Estimate

DATE	ESTIMATE #
4/23/2013	2662

Collin County
4600 Community Blvd
McKinney, TX 75071
Att: Ann Sadler

Job Site
Collin County Animal Shelter
4750 Community Blvd
McKinney, TX 75071

Project
Livestock Fencing Area

DESCRIPTION	QTY	COST	Total
Install new fence for area, 170 X 70 with 70' divider, 1 each gate, 2 3/8" pipe- 1 top rail, 1 middle rail, 1 bottom rail and combination panel welded to fence. (approx 575 linear feet)		14,780.00	14,780.00
Tie into outside water on existing building and run 1 each hydrant to edge of new gate.		2,780.00	2,780.00
Tie into existing light pole and install 1 each light pole (match existing) at edge of new gate. <i>Adding new breaker ✓</i>		11,370.00	11,370.00
Install 2 each 6" bollards at edge of new gate.		725.00	725.00
Drill and pour 4 each concrete piers for 7 different covers. Piers - approx 5' deep, 1' diameter - 2 #5 rebar in each pier (total of 28 piers)		5,130.00	5,130.00
Relocate existing covers on new piers, 7 each.		3,610.00	3,610.00

Gary Todd Watkins - (972)467-1925

Total **\$38,395.00**

ACCEPTED BY: _____, DATE _____, PREFERRED TIME FOR SCHEDULING: _____

PLEASE VERIFY FOOTAGE - (SQ FT, LINEAR FT, ETC.), (SQ. FT. IS ESTIMATE ONLY)

IF ESTIMATE IS ACCEPTED BY CUSTOMER, PLEASE SIGN AND DATE, FAX BACK TO (972)429-5703 or SCAN & SEND to info@gtconstruction-inc.com FOR SCHEDULING.

GT Construction, Inc. shall not be held liable for any such instances of occurrences for damages underground, including underground utilities. Equipment and materials supplied by the contractor are warranted to the extent of the manufactures warranty. Other exclusions: Permit fees and landscaping/sodding are not included unless stated on this estimate.

*Per Gary T.
Price still good
7/25-13
AG*

2013

Quote


DAL-EC

Animal Shelter

Ann Sadler

From: Don Wilbanks <don@dal-ec.com>
Sent: Tuesday, May 07, 2013 2:14 PM
To: Ann Sadler
Subject: Animal shelter corral

Ann
For the fence, carport piers, light pole and base, move carports, electric line, and water line my price came to \$39,000. Thanks for the opportunity.
Don



Custom Floor Service, Inc.

11129 Zodiac Ln. #300 Dallas TX 75229
Phone (214) 630-7202 Fax (214) 630-8993
www.cfsinc-dallas.com

Date: 7/17/2013
Proposal 903223

Collin County Animal Shelter
McKinney TX

Animal Corral

Proposed to: Ann Sadler

DESCRIPTION OF JOB

Furnish & install 170'x70' of 6' chain link fencing with 2 3/8" top rail and 2 center rails
Move 7 existing car to new area which will require 4 ea. 6'x 6" piers
total 28 piers & anchor car port
Relocate existing cattle panels to new area and erect
Furnish and Install electrical and new light pole to match existing light
Furnish and install new frost free water faucet
Cut 25 feet of concrete to get water and power run, trench 100 ft for water and power

1	Ea	\$42,000.00	\$42,000.00
		Proposal Total	\$42,000.00

A signed copy of this proposal by an authorized agent of above mentioned company must be faxed to **214-630-8993** before job will be started or materials ordered.
Thank You,

Scott Denton
CFS, Inc.

Approval Signature _____

Print Name _____

Title _____

Excludes (unless otherwise noted)
Holidays, Weekends, Overtime, Protection of Floorcoverings, Excessive Floor Prep (i.e. Floor Fill),
Vacuuming, Waxing, and Sealing of Tile, Furniture Moving, Moisture Testing, Demo, and Sales Tax

NOTES

- *Vapor Emissions must be 3#s or less for installation. CFS, Inc. cannot be responsible.
- for Moisture in Subfloor. Install ready as per CR104 acceptable subfloor conditions.
- **There will be a 15 day material bill on all large jobs.
- ***There will be a 1.5% late fee on all past due invoices.