

Hitchcock House Movers

308 Hitchcock Lane
Argyle, TN 37626
Office 940-241-2085 • Fax 940-241-2088
email: hirc2move@aol.com

~~INVOICE~~

- B i D -

DATE 2-4-13Bill To: COLLIN COUNTYMYER PARK & EVENT CENTER7117 CR. 166 MCKINNEY TX72-548-4792 OFF. 7507172-547-5743 FAXATTN: JUDY FLORENCEJENNIFER ROGERS

DESCRIPTION

AMOUNT

MOVE (2) HISTORIC STRUCTURES TO
NEW SLABS FOUNDATIONS ON SAME
SITE. SLABS TO BE FURNISHED BY OTHERS.

MOVE ONLY.#1. GRANARY\$4000.00#2. CONFINEMENT HOUSE\$4600.00Total: \$8600.00THO MARK H.

GT CONSTRUCTION, INC.

712 Lynda Lane
Wylie, TX 75098-4602
(972) 442 - 2213

Estimate

DATE	ESTIMATE #
5/23/2012	2223

Collin County
4600 Community Blvd
McKinney, Texas 75071
Attn: Mark Page

Job Site

Myers Park
7117 County Road 166
McKinney, TX 75071-7317

Project**Historical Buildings Foundations**

DESCRIPTION	QTY	COST	Total
Excavate areas S250 Bobcat, haul in 80 yards of Select Fil, build dirt pads for foundation. (contract item# 07115-07-20-01)		1,491.95	1,491.95
Installation of concrete pad 16 X 19, 15 X 27 - 5 inch concrete floor- exterior beam (1ft X 1ft), interior cross beam each way (1ft X 1ft). 9 each piers in 16 X 19 foundation, 12 each piers in 15 X 27 foundation. 1/2 inch rebar in floor 12 inch on center each way, 5/8 rebar in beam (2 top 2 bottom), 5/8 rebar in piers (2 each). Contract item# 07115-07-20-01	709	11.45	8,118.05
Gary Todd Watkins - (972)467-1925		Total	\$9,610.00

ACCEPTED BY: _____, DATE _____, PREFERRED TIME FOR SCHEDULING: _____

PLEASE VERIFY FOOTAGE - (SQ FT, LINEAR FT, ETC.), (SQ. FT. IS ESTIMATE ONLY)

IF ESTIMATE IS ACCEPTED BY CUSTOMER, PLEASE SIGN AND DATE, FAX BACK TO (972)429-5703 FOR SCHEDULING.

GT Construction, Inc. shall not be held liable for any such instances of occurrences for damages underground, including underground utilities. Equipment and materials supplied by the contractor are warranted to the extent of the manufactures warranty.