

Office of the Purchasing Agent 2300 Bloomdale Road Suite 3160 McKinney, Texas 75071 www.collincountytx.gov

COLLIN COUNTY, TEXAS

ADDENDUM No. Three (3) IFB No. 2019-032

**INVITATION FOR BID** 

FOR

#### CONSTRUCTION, RELOCATION OF COLLIN COUNTY TAX OFFICE, 900 E. PARK, PLANO

DATE: FEBRUARY 6, 2019

NOTICE TO ALL PROSPECTIVE BIDDERS:

PLEASE MAKE THE FOLLOWING CHANGES TO THE INVITATION FOR BID:

DELETE DOCUMENTS: A0-COVER

A4 FLOOR PLAN

**A5 SCHEDULES DETAILS** 

A7-HC ACCESS/LIFE SAFETY PLAN

**DE1-DEMOLITION ELECTRICAL LIGHTING PLANS** 

E1-ELECTRICAL LIGHTING PLANS E3-ELECTRICAL SCHEDULES M2-MECHANICAL SCHEDULES

REPLACE WITH: A0-COVER REV. 2/1/19

A4 FLOOR PLAN REV. 2/1/19

A5 SCHEDULES DETAILS REV. 2/1/19

A7-HC ACCESS/LIFE SAFETY PLAN REV. 2/1/19

DE1-DEMOLITION ELECTRICAL LIGHTING PLANS REV. 1

E1-ELECTRICAL LIGHTING PLANS REV. 1 E3-ELECTRICAL SCHEDULES REV. 1 M2-MECHANICAL SCHEDULES REV. 1

ADD: ACROVYN AS APPROVED MANUFACTURER UNDER SECTION 10 26 13-1, 2.01

ADD ATTRIBUTE: #21-ADDENDUM 3 ACKNOWLEDGEMENT

DELETE DOCUMENT: SECTION 004100-BID FORM ADDENDUM 2


REPLACE WITH: SECTION 004100-BID FORM ADDENDUM 3


ALL OTHER TERMS AND CONDITIONS OF THE BID AND SPECIFICATIONS REMAIN THE SAME.

SINCERELY,

MICHALYN RAINS, CPPO, CPPB

**PURCHASING AGENT** 





**ABBREVIATIONS** 

**AGGREGATE** 

AIR CONDITIONING

# ALLOWABLE HEIGHT: ACTUAL HEIGHT: 4 STORY 2 STORY FIRE PROTECTION: AUTOMATIC SPRINKLER SYSTEM **EXIT REQUIREMENTS** SEE SHEET A4


KILOWATT

KNOCKED DOWN

# TENANT FINISHOUT FOR

PARK PLAZA DEVELOPMENT 900 E. PARK BOULEVARD PLANO, TEXAS 75074 CONSTRUCTION DOCUMENTS







SPURGIN & ASSOCIATES ARCHITECTS MCKINNEY, TEXAS 75069

ROOT ENGINEERING SERVICES HOWE, TEXAS 75459

CROSS ENGINEERING CONSULTANTS, INC.

MCKINNEY, TEXAS 75069 GRUBBS DESIGN GROUP, PLLC **ENGINEERS LANDSCAPE ARCHITECT** 

ARCHITECT

MECH/ELEC ENGINEERS

# **COMMISSIONERS COURT**

KEITH SELF SUSAN FLETCHER CHERYL WILLIAMS

MCKINNEY, TEXAS 75069

COMMISSIONER-PRECINCT COMMISSIONER-PRECINCT 2 COMMISSIONER-PRECINCT COMMISSIONER-PRECINCT

# INDEX OF DRAWINGS

DEMOLITION FLOOR PLAN, NOTES DEMOLITION CEILING PLAN, NOTES
DEMOLITION FLOORING PLAN, NOTES NEW FLOOR PLAN, NOTES MISCELLANEOUS SCHEDULES DIMENSION CONTROL PLANS
HANDICAP ACCESSIBILITY / LIFE SAFETY PLAN
FLOORING PLAN, NOTES

REV 2/1/19

REFLECTED CEILING PLAN, NOTES INTERIOR ELEVATIONS

MILLWORK SECTIONS MILLWORK SECTIONS A14 MILLWORK SECTIONS A15 MILLWORK SECTIONS

DOOR, WINDOW & MISCELLANEOUS DETAILS DEMOLITION MECHANICAL PLANS MECHANICAL PLANS
MECHANICAL SCHEDULES, NOTES & DETAILS
MECHANICAL SCHEDULES, NOTES & DETAILS
DEMOLITION ELECTRICAL LIGHTING PLANS

DEMOLITION ELECTRICAL POWER PLANS ELECTRICAL LIGHTING PLANS ELECTRICAL POWER PLANS
ELECTRICAL SCHEDULES, NOTES & DETAILS
ELECTRICAL SCHEDULES, NOTES & DETAILS


LOW VOLTAGE PLANS LOW VOLTAGE NOTES & SCHEDULES
FIRE PROTECTION PLANS
FIRE PROTECTION SCHEDULES, NOTES & DETAILS DEMOLITION PLUMBING PLANS

P1 PLUMBING WATER PLANS
P2 PLUMBING WASTE/VENT PLANS
P3 PLUMBING SCHEDULES, NOTES & DETAILS
TAS1 2010 STANDARDS FOR ACCESSIBLE DESIGN
TAS2 2010 STANDARDS FOR ACCESSIBLE DESIGN
TAS3 2010 STANDARDS FOR ACCESSIBLE DESIGN
TAS4 2010 STANDARDS FOR ACCESSIBLE DESIGN
TAS5 2010 STANDARDS FOR ACCESSIBLE DESIGN


TASS 2010 STANDARDS FOR ACCESSIBLE DESIGN
TAS6 2010 STANDARDS FOR ACCESSIBLE DESIGN
--- CIVIL DRAWINGS/ENGINEERED SITE PLAN COVER
--- TOPOGRAPHIC SURVEY

SCSP SUBSTANTIALLY CONFORMING SITE PLAN C1-1 PAVING & DEMOLITION PLAN C2-1 GRADING PLAN C3-1 CONSTRUCTION DETAILS

PROJECT NUMBER: ISSUE DATE: OCT 2018 **SET NUMBER** 



OCATION MAP



**SPURGIN** 

& ASSOCIATES

ARCHITECTS

TENANT FINISHOUT FOR

PARK PLAZA DEVELOPMENT

900 E. PARK BOULEVARD

NEW FLOOR PLAN & ROOM FINISH NOTES

PLANO, TEXAS 75074

SHEET TITLE

PROJECT NUMBER

OCTOBER 2018


**FEBRUARY 1, 2019** 

ISSUE DATE

REVISION DATE

SHEET NUMBER

NUMBER OF EXITS PROVIDED:



HARDWARE NOTES:

1. ALL DOOR CONTROLS SHALL BE LEVER TYPE HANDLES COMPLYING WITH ADA & TAS STANDARDS FOR HANDICAP ACCESSIBILITY & SHALL NOT REQUIRE TIGHT GRASPING, PINCHING OR TWISTING OF THE WRIST. THE FORCE REQUIRED TO ACTIVATE OPERABLE PARTS SHALL BE 5 POUNDS MAXIMUM.


2. ALL EXIT DOORS SHALL BE OPENABLE FROM THE INSIDE WITHOUT THE USE OF A KEY OR ANY SPECIAL KNOWLEDGE OR EFFORT COMPLYING WITH APPLICABLE PROVISIONS OF THE UNIFORM BUILDING CODES CURRENTLY IN EFFECT.

3. HANDLES, PULLS, LATCHES, LOCKS & OTHER OPERABLE PARTS OF DOORS SUCH AS HARDWARE SHALL BE 34 INCHES MINIMUM & 48 INCHES MAXIMUM ABOVE THE FINISH FLOOR OR GROUND.

4. DOOR CLOSERS SHALL BE ADJUSTED SO THAT FROM AN OPEN POSITION OF 90 DEGREES, THE TIME REQUIRED TO MOVE THE DOOR TO A POSITION OF 12 DEGREES FROM THE LATCH IS 5 SECONDS MINIMUM. THE FORCE FOR PUSHING OR PULLING OPEN AN INTERIOR DOOR (OTHER THAN A FIRE DOOR) SHALL BE 5 POUNDS MAXIMUM.


5. THRESHOLDS SHALL BE 1/2 INCH HIGH MAXIMUM: CHANGES IN LEVEL OF 1/4 INCH HIGH MAXIMUM SHALL BE

5. THRESHOLDS SHALL BE 1/2 INCH HIGH MAXIMUM; CHANGES IN LEVEL OF 1/4 INCH HIGH MAXIMUM SHALL BE PERMITTED TO BE VERTICAL; CHANGES IN LEVEL BETWEEN 1/4 INCH HIGH MINIMUM & 1/2 INCH HIGH MAXIMUM SHALL BE BEVELED WITH A SLOPE NOT STEEPER THAN 1:2.



WET AREA FIXTURE/ACCESSORY PLAN






GLAZING SCHEDULE							
MARK	GLASS TYPE						
<u>1</u>	1" TINTED INSULATING GLASS, TEMPERED						
<u>^2</u>	1" TINTED INSULATING GLASS						
<u>3</u>	1/4" CLEAR PLATE GLASS						
4	1/4" CLEAR PLATE GLASS, TEMPERED						
<u> </u>	3/8" CLEAR PLATE GLASS, TEMPERED						


NO.	DESIGNATION	FLOOR	BASE	WALLS				CEILING		NOTES
				NORTH	EAST	SOUTH	WEST	MATL	HEIGHT	
101	LOBBY	VCT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
102	MV QUEUING	VCT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	NOTE 2
103	HC WAITING	VCT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
104	PT QUEUING	VCT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	NOTE 2
105	PT CLERKS	CPT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
106	STORAGE	VCT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
107	MV CLERKS	СРТ	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
108	CORRIDOR	СРТ	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
109	VAULT	VCT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
110	CASHIERS	CPT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
111	SUPERVISOR	CPT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
112	BACK-UP	CPT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
113	EMERGENCY EXIT	CPT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
114	MV CLERKS	CPT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
115	WEB CLERK	CPT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
116	MV CLERKS	CPT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
117	BREAK ROOM	VCT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
118	CORRIDOR	CPT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
119	IT	VCT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
120	ELECTRICAL	VCT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
121	VESTIBULE	CT-1	CT-1	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
122	MEN	CT-1	CT-1	CT-1	CT-1	CT-1	CT-1	ACT	8'-8"	
123	JANITOR	VCT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	NOTE 3 REV 2/1
124	CORRIDOR	CPT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	NOTE 1
125	VESTIBULE	CT-1	CT-1	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
126	WOMEN	CT-1	CT-1	CT-1	CT-1	CT-1	CT-1	ACT	8'-8"	
127	DEALER ROOM	CPT	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	
128	DEALER WAITING	СРТ	RBR	PNT-1	PNT-1	PNT-1	PNT-1	ACT	8'-8"	

NOTE 1: PROVIDE CERAMIC WALL TILE (CT-1) 6 FEET HIGH ON ALL 3 WALLS AT INSET AROUND DRINKING FOUNTAINS, 2 FT RETURN ON BOTH SIDE WALLS.

NOTE 2: WALL FINISH ON FACE OF MV & PT CLERK COUNTERS IS PLASTIC LAMINATE ON 1/2" PLYWOOD-SEE MILLWORK ELEVATIONS & SECTIONS FOR ADDITIONAL INFORMATION.

{NOTE 3: PROVIDE CERAMIC WALL TILE (CT-1) APPROX. 4 FEET HIGH ON 2'-6" EAST WALL & 5'-10" SOUTH WALL REV 2/1/19 ADJACENT TO MOP SINK.





NOTE: DF/HDF IS EXISTING FIXTURE REMOVED IN DEMO PHASE & INSTALLED IN NEW LOCATION PER FLOOR PLAN

PLUMBING FIXTURE SCHEDULE COMPLY W/AMERICANS WITH DISABILITIES ACT (ADA) & TEXAS ACCESSIBILITY STANDARDS (TAS)						
DESIG.	DESCRIPTION	MOUNTING HEIGHT (A.F.F. UNLESS NOTED)				
HSINK	HANDICAP ACCESSIBLE SINK (RIM/KNEESPACE)	34" MAX./27" MIN.				
LAV	LAVATORY (RIM)	36" MAX.				
HLAV	HANDICAP ACCESSIBLE LAVATORY (RIM/KNEESPACE)	34" MAX./27" MIN.				
UR	URINAL (RIM)	24"				
HUR	HANDICAP ACCESSIBLE URINAL (RIM/FLUSH CONTROL)	17" MAX./44" MAX.				
WC	WATER CLOSET (TOP OF SEAT)	15" TO TOP OF SEAT				
HWC	HANDICAP ACCESSIBLE WATER CLOSET (TOP OF SEAT/FLUSH CONTROL) (MOUNT FLUSH CONTROL ON WIDE SIDE OF TOILET AREA)	17"-19"/44" MAX.				
DF	DRINKING FOUNTAIN (SPOUT)	38"-43"				
HDF	HANDICAP ACCESSIBLE DRINKING FOUNTAIN (SPOUT/KNEESPACE)	36" MAX./27" MIN.				
MS	FLOOR MOUNTED MOP SINK	NA				

TO	ILET ACCESSORY	SCHEDULE	
DESIG.	DESCRIPTION (10810 UNLESS NOTED)	MANUFACTURER/MODEL	MTG. HEIGHT (FROM F.F. UNLESS NOTED)
TA1	TOILET PARTITIONS	SANTANA HDPE PLASTIC	FLOOR MOUNTED, HEADRAIL BRACED
TA2	36" GRAB BARS (MOUNT 6" FROM CORNER)	BRADLEY 8120-001 36"	33-36" TO TOP OF BAR
TA3	42" GRAB BARS (MOUNT 12" FROM CORNER)	BRADLEY 8120-001 42"	33-36" TO TOP OF BAR
TA4	TOILET PAPER DISPENSER	KIMBERLY CLARK 09551	15"-48" TO TISSUE ACCESS
TA5	TOWEL DISPENSER	KIMBERLY CLARK 09765	42" TO PAPER SLOT
TA6	SOAP DISPENSER	KIMBERLY CLARK 92144	40" TO VALVE
TA7	SEMI-RECESSED WASTE RECEPTACLE	BRADLEY 346-10	32" TO WASTE RECEPTACLE TOP LIP
TA8	FEMININE NAPKIN DISPOSAL	BRADLEY 4722-15	32" TO TOP OF UNIT
TA9	MOP AND BROOM HOLDER	BRADLEY 9954 X 36"	60" TO TOP OF HOLDER



CARPET (CPT):

MANUFACTURER: TANDUS/CENTIVA AFTERMATH II

PRODUCT: AFTERMATH II 03026 24" TILE

COLOR: TAPESTRY #23512

COLOR: TAPESTRY #23512
APPLICATION: PER MFR RECOMMENDATIONS

VINYL COMP. TILE (VCT):
MANUFACTURER: ARMSTRONG OR AZROCK

MANUFACTURER: ARMSTRONG OR AZROCK
PRODUCT: 12" X 12" X 1/8"
COLOR: TBD
APPLICATION: PER MFR RECOMMENDATIONS

RUBBER BASE (RBR):
MANUFACTURER: JOHNSONITE

PRODUCT: BASEWORKS 4" WALL BASE WITH TOE COLOR: 18 NAVY BLUE (AT CARPET)
TBD (AT VCT)
APPLICATION: NEATLY FORM INSIDE & OUTSIDE

APPLICATION: NEATLY FORM INSIDE & OUTS CORNERS FROM ROLL STOCK

CERAMIC TILE (CT-1):

MANUFACTURER: DAL-TILE

PRODUCT: COTTO CONTEMPO 13" X 13" TILE COLOR: CC15 SUNSET BLVD APPLICATION: PER MFR RECOMMENDATIONS

PAINT (PNT-1):

MANUFACTURER: SHERWIN WILLIAMS
PRODUCT:

AS APPROPRIATE F


PRODUCT:
COLOR:
AS APPROPRIATE FOR SUBSTRATE
TBD
APPLICATION:
PER MFR RECOMMENDATIONS, 1COAT
PRIMER & 2 COATS PAINT

ACOUSTIC CEILING TILE (ACT)
MANUFACTURER: ARMSTRONG

PRODUCT: 2' X 4' 755 FISSURED, SQ EDGE COLOR: WHITE APPLICATION: PER MFR RECOMMENDATIONS IN 15/16" EXPOSED T—GRID SYSTEM

NOTE: ALL EXISTING PREFINISHED STEEL DOOR FRAMES SCHEDULED TO BE RE-USED HAVE PREVIOUSLY BEEN PAINTED & SHALL BE RE-PAINTED AS PART OF THE WORK OF THIS PROJECT.









TENANT FINISHOUT FOR

TAX ACCESSOR COLLECTOR

PARK PLAZA DEVELOPMENT 900 E. PARK BOULEVARD PLANO, TEXAS 75074

SHEET TITLE

MISCELLANEOUS SCHEDULES/DETAILS

SCHEDULES/DETAILS


PROJECT NUMBER


1801
ISSUE DATE

OCTOBER 2018
REVISION DATE

FEBRUARY 1, 2019
SHEET NUMBER


**A5** 








PLAN / LIFE SAFETY




ELECTRICAL SYMBOL LEGEND

DEMOLITION ELECTRICAL

XX Check By XX





☐ DISCONNECT SWITCH

Junction Box

POWER FOR HEATER (SPACE, WATER, ETC.). REFER TO SCHEDULES, ELECTRICAL/PLUMBING DRAWINGS

TRANSFORMER AS INDICATED EMERGENCY FIXTURE WITH ADDITIONAL UNSWITCHED POWER TO BATTERY PACK

EXIT LIGHT, REFER TO SCHEDULE ₩ALL MOUNTED INTERIOR EMERGENCY LIGHT, REFER TO SCHEDULE

SURFACE MOUNTEDEXTERIOR EMERGENCY LIGHT, REFER TO SCHEDULE

A=LIGHT FIXTURE TYPE, B=CIRCUITING PANEL, \*=CIRCUIT NUMBER
B-# US

A=LIGHT FIXTURE TYPE, B=CIRCUITING PANEL, \*=CIRCUIT NUMBER

COMBINATION MOTOR STARTER/ DISCONNECT SWITCH, AS NOTED

CIRCUIT SYMBOL. THIS EXAMPLE SHOWS I GROUND, I NEUTRAL, I HOT IN CONDUIT.

CIRCUIT SYMBOL. THIS EXAMPLE SHOWS I GROUND, I NEUTRAL, 2 HOT IN CONDUIT.

CIRCUIT SYMBOL. THIS EXAMPLE SHOUS | GROUND, | NEUTRAL, 3 HOT IN CONDUIT. → CHANGE IN CONDUIT ELEVATION

S SPEAKER

(P) HEADPHONE JACK FOR HEARING IMPAIRED

MOMERUN SYMBOL. THIS EXAMPLE SHOWS TWO POLES

PANELBOARD (SEE SCHEDULE)

PLYWOOD TELEPHONE BACKBOARD, 4"X4"X3/4" THICK WITH TWO COATS OF INSULATING

DUPLEX RECEPTACLE WITH A = PANEL AND \* = CIRCUIT, REFER TO DETAILS FOR MOUNTING HEIGHT UNLESS OTHERWISE NOTED: INTERRUPTING, WP IN USE-WEATHERPROOF IN USE, IG=ISOLTED GROUND, E=EXISTING, GFI=GROUND FAULT INTERUPT.

DOUBLE DUPLEX (QUADRUPLEX) RECEPTACLE REFER TO DETAILS FOR MOUNTING HEIGHT UNLESS OTHERWISE NOTED HALF AUTOMATICALLY CONTROLLED DUPLEX / QUADRUPLEX RECEPTACLE REFER TO NOTE FOR SCHEDULE AND WIRING DUPLEX / QUADRUPLEX RECEPTACLE WITH USB POWER

SPECIAL PURPOSE OUTLET WITH GROUND

▼ TELEPHONE/DATA OUTLET IN WALL, REFER TO DETAIL FOR MOUNTING, HEIGHT UNLESS OTHERWISE NOTED. C=CONSOLE STATION PHONE

\$x SINGLE POLE (UNLESS OTHERWISE NOTED) SWITCH 120/277 $\lor$ , 48"AFF UNLESS OTHERWISE NOTED

 $\hbox{-4=FOUR-WAY, -$C=$PEED}\ \ \hbox{\it CONTROL,}\ \ d=DIMMER,\ k=KEYED.\ \ REFER\ \ \hbox{\it TO}\ \ SWITCH\ \ SCHEDULE$ 

\$ MOTOR RATED SWITCH

\$PILOT SWITCH \$ MOTION OR OCCUPANCY SWITCH - REFER TO SCHEDULE

FACP FIRE ALARM CONTROL PANEL FAAP FIRE ALARM ANNUNCIATOR PANEL

FIRE ALARM PULL STATION, 48" AFF, ADA COMPLIANT W/ WIREGUARD

III MAGNETIC HOLD-OPEN

 $\stackrel{ extstyle imes}{ imes}$  fire alarm audio-visual annunciator wall mounted at 80" AFF, ada compliant, am www.www.www.mireguard.triangle shous direction of visual component. WP = weatherproof

DOOR HOLD OPEN DEVICES

FIRE ALARM SPEAKER ANNUNCIATOR


FIRE ALARM VISUAL ANNUNCIATOR, 80" AFF, ADA COMPLIANT

TAMPER SWITCH

SD) SMOKE DETECTOR

(SD) SMOKE DETECTOR, DUCT MOUNTED, FURNISHED BY MECH SUB, CONNECTED BY ELECT. FIRE DEPARTMENT CONNECTION FOR FIRE PROTECTION LINE

- $\langle 1 \rangle$  Existing to remain electrical / data / fire alarm / fire protection DEVICE UNLESS NOTED OTHERWISE. REWORK WITH NEW WALL / CEILING / FLOOR
- $\langle 2 
  angle$  EC TO FURNISH AND INSTALL NEW ELECTRICAL / LIGHT / POWER / DATA / FIRE ALARM / FIRE PROTECTION DEVICE(S) AS SHOWN. EC TO REUSE EXISTING LOCAL
- (3) EC TO RELOCATE EXISTING ELECTRICAL / LIGHT / POWER / DATA / FIRE ALARM / FIRE PROTECTION DEVICE(S) TO LOCATION SHOWN.
- (4) DATA CONDUIT TO BE INDIVIDUAL 3/4" (MINIMUM) CONDUIT FROM DATA JACK TO ABOVE CEILING. COMBINING OF CONDUITS IS PROHIBITED UNLESS NOTED OTHERWISE, INCLUDE ONLY ONE DATA JACK / TERMINATION UNLESS NOTED OTHERWISE, TYPICAL OF DATA OUTLETS.
- (5) "DAISY CHAINING" OF GFI RECEPTACLES IS PROHIBITED. EACH RECEPTACLE TO BE GFI. TYPICAL OF GFI RECEPTACLES.
- 1 DUCT MOUNTED SMOKE DETECTOR FURNISHED AND INSTALLED BY FPC.
- (8) OVERSIZED CONDUITS TO FEED INDIVIDUAL PANIC BUTTONS (BY OTHERS).




PROJECT CC TA SOO E. PARI PLANO, TE


DRAWING ISSUE / REVISION							
1	Description	Date					
	FOR PERMIT ADDENDUM #3	12/03/2018 02/04/2019					
rofessional seal affixed to this sheet tes that the named professional has prepared scted the preparation of the material shown on this sheet. Other drawings and							

undersigned. Copyright © 2018 Root Engineering. LECTRICAL LIGHTING PLANS

XX Check By







ELECTRICAL SCHEDULES,

XX Check By XX

			Project Name	CC TAC Office					Date	5/15/2018					
ROOM NUMBER	ROOM NAME	AREA (SF)	OCCUPANCY CLASSIFICATION	APPLICABLE VENTILATION CODE	OCCUPANCT COUNT	WATER CLOSET COUNT	BREATHING ZONE OA	ZONE AIR EFFECTIVENESS	ZONE OUTDOOR AIRFLOW	REQUIRED EXH	ROOM SUPPLY	ROOM EXHAUST	ACTUAL OA	SYSTEM	% OUTSIDE AII
101	Vestibule	89	Public	Corridors	0	0	5	0.80	7	0	280	0	29	AHU-7	10%
102	MV Queuing	1110	Offices	LOBBIES-office	11	0	122	0.80	152	0	690	0	127	AHU-9	18%
103	HC Waiting	77	Offices	LOBBIES-office	6	0	35	0.80	43	0	240	0	25	AHU-7	10%
104	PT Queuing	423	Offices	LOBBIES-office	4	0	45	0.80	57	0	835	0	87	AHU-7	10%
105	PT Clerks	240	Offices	OFFICE SPACES	4	0	34	0.80	43	0	250	0	33	AHU-5	13%
106	Storage	220	Retail	STORAGE ROOMS	0	0	26	0.80	33	0	480	0	64	AHU-5	13%
107	MV Clerks	352	Offices	OFFICE SPACES	5	0	46	0.80	58	0	415	0	76	AHU-9	18%
108	Corridors	49	Public	Corridors	0	0	3	0.80	4	0	25	0	5	AHU-9	18%
109	Vaults	131	Retail	STORAGE ROOMS	0	0	16	0.80	20	0	75	0	10	AHU-5	13%
110	Cashiers	226	Offices	OFFICE SPACES	3	0	29	0.80	36	0	320	0	43	AHU-5	13%
111	Supervisor	150	Offices	OFFICE SPACES	1	0	14	0.80	18	0	260	0	35	AHU-5	13%
112	Back up	248	Offices	OFFICE SPACES	5	0	40	0.80	50	0	295	0	39	AHU-5	13%
113	Emergency Exit	189	Public	Corridors	0	0	11	0.80	14	0	320	0	43	AHU-5	13%
114	MV Clerks	165	Offices	OFFICE SPACES	2	0	20	0.80	25	0	300	0	17	AHU-11	6%
115	Web Clerk	149	Offices	OFFICE SPACES	1	0	14	0.80	17	0	360	0	20	AHU-11	6%
116	MV Clerks	660	Offices	OFFICE SPACES	10	0	90	0.80	112	0	820	0	151	AHU-9	18%
117	Break Room	315	Offices	LOBBIES-office	3	0	34	0.80	42	0	715	0	40	AHU-11	6%
118	Corridors	36	Public	Corridors	0	0	2	0.80	3	0	25	0	5	AHU-9	18%
119	IT	97	NoStandard	No Standard	_	0	-	0.80		_	600	0	0	AHU-IT	0%
120	Elec	72	NoStandard	No Standard	-	0	-	0.80	-	_	25	0	1	AHU-11	6%
121	Vestibule	35	Public	Corridors	0	0	2	0.80	3	0	25	0	1	AHU-11	6%
122	Mens RR	163	Public	TOILET ROOMS-Public (high use)	0	3	0	0.80	0	210	75	225	4	AHU-11	6%
123	Janitor	66	NoStandard	No Standard	-	0	-	0.80	-	-	0	75	0	AHU-11	6%
124	Corridors	38	Public	Corridors	0	0	2	0.80	3	0	25	0	5	AHU-9	18%
125	Vestibule	35	Public	Corridors	0	0	2	0.80	3	0	25	0	1	AHU-11	6%
126	Women's RR	188	Public	TOILET ROOMS-Public (high use)	0	3	0	0.80	0	210	75	225	4	AHU-11	6%
127A	Dealer Room Interior	273	Offices	OFFICE SPACES	4	0	36	0.80	45	0	285	0	29	AHU-13	10%
128	Dealer Waiting	79	Offices	LOBBIES-office	6	0	35	0.80	43	0	245	0	26	AHU-7	10%
127B	Dealer Room Exterior	268	Offices	OFFICE SPACES	1	0	36	0.80	45	0	715	0	72	AHU-13	10%
1270	Dealer Room Exterior	200	Ollides	OFFICE OF AGEO	-		30	0.00	40		710		12	A110-10	1070
UNIT	OA %	PRIMARY OA	SYSTEM VENTILATION EFFICIENCY	UNCORRECTED OA INTAKE FLOW	CORRECTED	OA INTAKE FLOW	UNIT SIZE	MIXED AIRFLOW	O.A.	ACTUAL AIR	MIX FLOW 1	MIX FLOW	ACTUAL AIR	ACTUAL -	1
AHU-9	18%	FRACTION 22%	0.9	330.875	367	.6388889	(TONS)	2000	367.6388889	FLOW 1 2000	0	2	FLOW 2000	SUPPLY	+
AHU-5	13%	26%	0.8	212.875	200000	6.09375	5	2000	266.09375	2000	0	0	2000	0	+
AHU-7	10%	18%	0.8	150.1		.7777778	4	1600	166.7777778	1600	0	0	1600	0	+
AHU-13	10%	16%	0.9	90.575		.6388889	2.5	1000	100.6388889	1000	0	0	1000	0	+
AHU-13 AHU-11	6%	11%	1.0	90.575 89.925		.638889 39.925	2.5	1600	89.925	1600	0	0	1600	0	+
AHU-IT	0%	0%	1.0	89.925		0	1.5	600	89.925	600	0	0	600	0	+
AUU-II	U%	U%	1.0	0		U	1.5	600		600	U		000	U	
			0.8	874.35	004	.0743056	22	8800	991.0743056	8800	0	0	8800	0	7

## CONTROL NOTES

CONTRACTOR SHALL PROVIDE NEW WALL MOUNTED CARRIER SPACE TEMPERATURE SENSOR FOR EACH UNIT (M/N T-55 WITHOUT SLIDEBAR), CONNECT TO EXISTING UNIT CONTROLLER. CONTROLLER SHALL ENABLE CONTINUOUS FAN OPERATION DURING ALL OCCUPIED HOURS. DURING UNOCCUPIED HOURS FAN SHALL CYCLE WITH CALL FOR HEAT/COOL.

## EQUIPMENT SCHEDULE

AHU-AHU-5, 7, 9, 11, 13, IT: EXISTING SPLIT SYSTEMS. MC TO FURNISH AND INSTALL HONEYWELL FIØØ 4" FILTER. CHECK A/C CHARGE, CLEAN CONDENSER COIL. MC TO CONFIGURE CONTROLLER SUCH THAT FAN RUNS DURING OCCUPIED HOURS. CONFIGURE FOR LOW AMBIENT COOLING.

FILTER BOX: 20X25X4 HONEYWELL FIDO 4" FILTER (FOR SUPPLY FAN).

## GENERAL MECHANICAL NOTES

- THE MECHANICAL SUBCONTRACTOR SHALL PROVIDE A COMPLETE AND USABLE SYSTEM WITHIN | 10 | ELECTRICAL CONNECTIONS 120V OR HIGHER SHALL BE THE RESPONSIBILITY OF THE THE INTENT AND SPIRIT OF THAT INDICATED BY THIS DRAWING, WORK OR MATERIALS NOT SHOWN ! BY THIS DRAWING, BUT NECESSARY TO COMPLETE THE SYSTEM SHALL BE INCLUDED AT NO ADDITIONAL COST, THE MECHANICAL SUBCONTRACTOR SHALL FURNISH AND INSTALL ALL HYAC SYSTEM REQUIREMENTS INCLUDING GRILLES, DIFFUSERS, DUCTWORK, CONTROLS, CONTROL WIRING, DUCTWORK, EQUIPMENT, HYAC PIPING, CUTTING AND PATCHING, ETC.
- THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS, MAKE ADJUSTMENTS TO AVOID CONFLICT. NOTIFY THE ENGINEER IN WRITING OF SIGNIFICANT CONSTRUCTABILITY ISSUES.
- PROVIDE VOLUME DAMPERS WHERE INDICATED.
- ALL RECTANGULAR AND ROUND DUCTWORK SHALL BE GALYANIZED SHEET METAL, FABRICATED AND SUPPORTED TO SMACNA STANDARDS, ALL SUPPLY DUCT SHALL HAVE 2", 1.5\* BLANKET INSUL W/ YAPOR BARRIER (R-8). EXPOSED DUCTWORK THAT IS ROUND TO BE SPIRAL AND TO HAVE I" LINER, INSIDE DIAMETER AS SHOWN, FURNISH AND INSTALL NEOPRENE FLEX CONNECTION BETWEEN DUCTWORK AND RTUS/AHUS.
- FLEXIBLE DUCT SHALL BE FLEXMASTER TYPE Y OR EQUAL FIBERGLASS INSULATED TYPE. FLEX DUCT SHALL NOT EXCEED 6' IN LENGTH. RIGID ROUND DUCT WITH EXTERIOR INSULATION. USE RIGID ROUND DUCT WITH EXTERIOR INSULATION ABOVE WHERE SHOWN ON THE PLAN. USE RIGID ELBOW FITTINGS WHENEVER POSSIBLE TO AVOID UNNECESSARY CHANGE OF DIRECTION WITH FLEXDUCT.
- SEAL ALL DUCTWORK SEAMS WITH FIBERGLASS TAPE IMBEDDED IN ARABOL SEALER OR ALUMINUM TAPE. DUCT TAPE IS NOT ACCEPTABLE. VAPOR SEAL ALL EXTERIOR INSULATION WITH | 15 ALUMINUM TAPE. DUCT TAPE IS NOT ACCEPTABLE.
- CONTRACTOR SHALL ADJUST CURB PLACEMENT AND TRANSITION DUCTWORK AS REQUIRED TO CLEAR STRUCTURAL AND OTHER OBSTACLES, THE CONFIGURATION OF THE STRUCTURE AND OTHER OBSTACLES IN THE EXISTING BUILDING IS NOT KNOWN IN DETAIL. THE CONTRACTOR WILL INVESTIGATE, VERIFY THE DESIGN SHOWN, AND ADJUST AS REQUIRED.
- ALL WORK SHALL COMPLY WITH APPLICABLE CODES, REGULATIONS, LAWS AND THE DETERMINATIONS OF THE LOCAL BUILDING OFFICIAL AT NO EXTRA COST. THE CONTRACTOR SHALL INFORM THE ENGINEER IN WRITING OF ANY CONFLICT BETWEEN THE PLANS AND APPLICABLE CODES.
- ALL MATERIALS WILL BE NEW AND IN NEW CONDITION, SCRATCH AND DENTED, SECONDHAND, SURPLUS, ETC ARE NOT ACCEPTABLE.

- ELECTRICAL SUBCONTRACTOR, MECHANICAL SHALL COORDINATE THIS WORK, MECHANICAL SHALL FURNISH DUCT SMOKE DETECTORS AS REQUIRED TO ELECTRICAL FOR FIRE ALARM INSTALLATION.
- THE MECH SUBCONTRACTOR SHALL START UP EACH UNIT, TEST FOR HEAT AND COOL OPERATION, INSURE ALL DUCTWORK IS FREE OF RATTLES, LEAKS, WHISTLES, ETC. AN INDEPENDENT CONTRACTOR SHALL BALANCE THE SYSTEM AS INDICATED BY DRAWINGS, RTU SCHEDULE, AND VENTILATION SCHEDULES, SUBMIT FOUR COPIES OF A CERTIFIED TEST AND BALANCE REPORT TO THE ARCHITECT FOR APPROVAL, UPON APPROVAL CONTRACTOR SHALL FILE REPORT WITH LOCAL AUTHORITY.
- WHEN SYSTEMS ARE COMPLETE AND OPERATIONAL, A 'PUNCH LIST' INSPECTION SHALL BE REQUESTED BY THE CONTRACTOR, SUCH AN INSPECTION SHALL NOT BE CONDUCTED ON INCOMPLETE OR NON-OPERATIONAL SYSTEMS.
- ALL DUCTWORK (SUPPLY AND RETURN) IN UNCONDITIONED SPACES SHALL BE INSULATED WITH A MINIMUM VALUE OF R-5 INSULATION. ALL DUCTS OUTSIDE OF THE BUILDING ENVELOPE SHALL BE INSULATED WITH R-8 MINIMUM.
- DUCTS SHALL BE SUPPORTED WITH APPROVED HANGERS AT INTERVALS NOT EXCEEDING 10 FEET OR BY OTHER APPROVED DUCT SUPPORT SYSTEMS DESIGNED IN ACCORDANCE WITH THE INTERNATIONAL MECHANICAL CODE, FLEXIBLE AND OTHER FACTORY MADE DUCTS SHALL BE SUPPORTED IN ACCORDANCE WITH THE MANUFACTURERS INSTRUCTIONS.
- SMOKE DETECTORS SHALL BE INSTALLED IN RETURN AIR SYSTEMS WITH A DESIGN CAPACITY GREATER THAN 2000 CFM IN THE RETURN AIR DUCT OR PLENUM UPSTREAM OF ANY FILTERS. EXHAUST AIR CONNECTIONS, OUTDOOR AIR CONNECTIONS, OR DECONTAMINATION EQUIPMENT AND APPLIANCES.
- UPON SELECTION OF MECHANICAL APPLIANCES SUBMIT MANUFACTURING INSTALLATION INSTRUCTION TO BUILDING DEPARTMENT, INCLUDE ANY LISTING FOR OUTDOOR INSTALLATION, IF APPLICABLE.
- EQUIPMENT SHALL BE INSTALLED AS REQUIRED BY THE TERMS OF THEIR APPROVAL, IN ACCORDANCE WITH THE CONDITIONS OF THE LISTING, THE MANUFACTURERS INSTALLATION INSTRUCTIONS AND APPLICABLE CODES. MANUFACTURERS INSTALLATION INSTRUCTIONS SHALL BE AVAILABLE ON THE JOB SITE FOR INSPECTION.
- ALL COVERING, LININGS, ADHESIVES, WHEN USED SHALL HAVE A FLAME SPREAD RATING NOT MORE THAN 25 AND SMOKE DEVELOPED RATING NOT MORE THAN 50 WHEN TESTED IN ACCORDANCE WITH ASTM-E84.


		AIF	RDEVI	CE SCHE!	DULE	
MARK	TYPE	NECK SIZE	FACE SIZE	THROW PATTERN	MOUNTING	TITUS OR AS INDICATED
Д	DIRECTIONAL CEILING DIFFUSER	6"ø	24"×24"	4-WAY	LAY-IN	TMS 6 24x24 326
В	DIRECTIONAL CEILING DIFFUSER	6"ø	12"×12"	4-WAY	LAY-IN	TMS 6 12x12 326
С	CUBE CORE CEILING RETURN	22"×1Ø"	24"x12"	-	LAY-IN	5ØF
D	CUBE CORE CEILING RETURN	22"×22"	24"×24"	-	LAY-IN	5ØF
E	DIRECTIONAL CEILING DIFFUSER	8"¢	24"×24"	4-WAY	LAY-IN	TMS 8 24×24 326
F	LINEAR SLOT INSULATED BOOT PLENUM	1Ø"ø	4"x48"	2-WAY	LAY-IN	TBDI-10 48 IHP 8 1 1/2 02 0
G	DIRECTIONAL CEILING DIFFUSER	12"ø	24"×24"	4-WAY	LAY-IN	TMS 12 24x24 326
Ť	THERMAL CONTROLLED CEILING DIFFUSER	<b>6</b> "ø	24"x24"	4-WAY	LAY-IN	ACUTHERM ST-HC-6 150 CFM

- 1. MECHANICAL CONTRACTOR TO PROVIDE SQUARE TO ROUND TRANSITIONS AS REQUIRED. PROVIDE LAY-IN FRAME WHERE
- 2. ALL DEVICES SHALL BE METAL-AIRE, TITUS, T & B, OR APPROVED EQUAL (UNLESS NOTED OTHERWISE) COMPLETE WITH V.D.
- 3. ALL FRAMING REQUIRED FOR DIFFUSER INSTALLATION SHALL BE BY THE GENERAL CONTRACTOR 4. SEE MECHANICAL PLAN FOR DIFFUSER LOCATIONS

		FAN	SCHE	- DUL		
MARK	EF-1	EF-2A,B	SF-1			
BRAND	COOK	COOK	COOK			
MODEL NO.	GC-148	GC-442	1005QN-B			
CFM	75	225	1000			
SP	.5	.5	.8			
WATTS (HP)	31	81	(3/4)			
MAX SONES	e.	4.0	15.4			
VOLTAGE IPH	120	12Ø	208			
NOTES	1-6	1-6	1-2,5-7			
NOTES	•				*	

- INCLUDE BACKDRAFT DAMPER
- INCLUDE DISCONNECT ACCESSORY 3. FIELD VERIFY 10' CLEARANCE TO ANY OAI, IF EXHAUST
- 4. PROVIDE ALUMINUM GRILLE
- 5. PROVIDE 120V FAN SPEED CONTROLLER PREWIRED IF DIRECT SPEED FAN.
- PROVIDE BELT TENSIONER ROTARY IF BELT DRIVE.
- 6. MOUNT WITH YIBRATION ISOLATORS 7. FURNISH AND INSTALL WITH BELT GUARD.





ADDENDUM #3 The Professional seal affixed to this sheet indicates that the named professional has prepared or directed the preparation of the material shown only on this sheet. Other drawings and documents not exhibiting this seal shall not be considered prepared by or the responsibility of the undersigned.

undersigned. Copyright © 2018 Root Engineering. MECHANICAL SCHEDULES

NOTES AND DETAILS

XX Check By XX

### Section 004100-Bid Form Addendum 3



## 2019-032 Addendum 3

# Construction, Relocation of Collin County Tax Office, 900 E. Park, Plano

Issue Date: 1/8/2019

Questions Deadline: 2/8/2019 03:00 PM (CT) Response Deadline: 2/14/2019 02:00 PM (CT)

Collin County Purchasing

#### **Contact Information**

Contact: JD Griffin, CPPB Buyer II Address: 2300 Bloomdale Rd.

Ste. 3160 Purchasing Admin. Building

Ste.3160

McKinney, TX 75071

Phone: (972) 548-4116 Fax: (972) 548-4694

Email: jgriffin@co.collin.tx.us

Page 1 of 12 pages Deadline: 2/14/2019 02:00 PM (CT) 2019-032 Addendum 3

#### **Event Information**

Number: 2019-032 Addendum 3

Title: Construction, Relocation of Collin County Tax Office, 900 E. Park, Plano

Type: Invitation for Bid - Construction

Issue Date: 1/8/2019

Question Deadline: 2/8/2019 03:00 PM (CT) Response Deadline: 2/14/2019 02:00 PM (CT)

Notes: Please log in to view bid documents.

#### **Ship To Information**

Address: 900 E. Park Blvd.

Suite 100

Plano, TX 75074

#### **Billing Information**

Address: 2300 Bloomdale Rd.

Ste. 3100 Auditor

Admin. Building

Ste. 3100

McKinney, TX 75071

#### **Bid Activities**

#### **Mandatory Pre-Bid Conference**

1/22/2019 1:30:00 PM (CT)

A MANDATORY PRE-BID CONFERENCE will be held by Collin County at 900 E. Park Blvd, Suite 100, Plano TX 75074 on Tuesday, January 22, 2019 at 1:30 PM in order for bidders to ask questions regarding the proposed work. All bidders desiring to bid the work should have a representative at the pre-bid conference; bidders that do no attend the pre-bid conference shall not be considered in the evaluation for award of a contract per Texas Local Government Code 262.0256. Attendance shall be mandatory at the pre-bid conference.

#### **Optional Site-Walk**

1/30/2019 10:00:00 AM (CT)

An Optional Site-Walk will be held at 900 E. Park Blvd, Suite 100, Plano TX 75074 on Wednesday, January 30, 2019 at 10:00 AM in order for attendees of the January 22 Mandatory Pre-Bid Conference to verify field conditions regarding the proposed work.

Intent to Bid 2/8/2019 5:00:00 PM (CT)

Do you intend to submit a bid?

#### **Bid Attachments**

Addendum 3 2019-032.doc

**View Online** 

Addendum 3

Addendum 2\_2019-032.doc View Online

Addendum 2

Addendum 1\_2019-032.doc View Online

Addendum 1

LEGAL NOTICE-2019-032.doc Download

Legal Notice

Specifications\_2019-032.pdf View Online

**Specifications** 

Page 2 of 12 pages Deadline: 2/14/2019 02:00 PM (CT) 2019-032 Addendum 3

Plans\_2019-032.pdf View Online

**Plans** 

Sign-In Sheet\_1-22-19.pdf View Online

1/22/2019 Pre-Bid Sign-In Sheet

C2-2 Erosion Control Plan.pdf View Online

C2-2 Erosion Control Plan

28 31 00 Fire Detection and Alarm\_Revised.pdf View Online

Section 28 31 00 Fire Detection and Alarm Revised

06 40 00 Architectural Woodwork Revised.pdf View Online

Section 06 40 00 Architectural Woodwork Revised

A0 Cover Revised 2-1-19.pdf View Online

A0-Cover Revised 2-1-19

A4 Floor Plan Revised 2-1-19.pdf View Online

A4-Floor Plan Revised 2-1-19

A5 Schedules Details Revised 2-1-19.pdf View Online

A5-Schedules Details Revised 2-1-19

A7 HC Access and Life Safety Plan Revised 2-1-19.pdf View Online

A7-HC Access and Life Safety Plan Revised 2-1-19

DE1\_Rev 1.pdf View Online

DE1-Demolition Electrical Lighting Plans Rev. 1

E1\_Rev 1.pdf View Online

E1-Electrical Lighting Plans Rev. 1

E3\_Rev 1.pdf View Online

E3-Electrical Schedules Rev. 1

M2\_Rev 1.pdf View Online

M2-Mechanical Schedules Rev. 1

### **Requested Attachments**

#### **Bid Bond**

(Attachment required)

All Bidders must submit, prior to the bid opening time, a Cashier's Check or acceptable Bid Bond payable without recourse to Collin County in the amount of not less than five percent (5%) of the total bid plus alternates as submitted.

Bid Bond or Cashier's Check may be mailed or hand delivered to the Office of the Collin County Purchasing Agent, Collin County Administration Building, 2300 Bloomdale Road, Ste 3160, McKinney, TX 75071 BID SECURITY: All Bidders must submit, prior to the bid opening time, a certified check, Cashier's Check or acceptable Bid Bond payable without recourse to Collin County in the amount of not less than five percent (5%) of the total bid plus alternates as submitted.

- 1. Bid Bond, certified check or Cashier's Check may be mailed or hand delivered to the Office of the Collin County Purchasing Agent, Collin County Administration Building, 2300 Bloomdale Road, Ste 3160, McKinney, TX 75071 and shall be delivered in an envelope, marked plainly on the outside with the Bid Name and Number.
- 2. Bidders submitting a bid via Collin County eBid shall upload a Bid Bond at https://collincountytx.ionwave.net

Regardless of delivery method, all Bid Bonds shall be received prior to the bid opening time to be considered. Failure to submit a copy of bid security prior to bid opening shall be cause for rejection of bid.

Page 3 of 12 pages Deadline: 2/14/2019 02:00 PM (CT) 2019-032 Addendum 3

#### 2270 Verification

(Attachment required)

W-9

(Attachment required)

#### **Conflict of Interest Questionnaire**

#### **Bid Attributes**

	- 1 · · · · · · · · · · · · · · · · · ·
4	a Dist Martin
1	Collin County exclusively uses IonWave Technologies, Inc. (Collin County eBid) for the notification and dissemination of all solicitations. The receipt of solicitations through any other means may result in your receipt of incomplete specifications and/or addendums which could ultimately render your bid/proposal non-compliant. Collin County accepts no responsibility for the receipt and/or notification of solicitations through any other means. Please initial.  (Required: Maximum 1000 characters allowed)
2	Contact Information
_	List the contact name, email address and phone number of the main person(s) Collin County should contact in reference to this solicitation. Contact(s) shall be duly authorized by the company, corporation, firm, partnership or individual to respond to any questions, clarification, and or offers in response to this solicitation.
	(Required: Maximum 4000 characters allowed)
3	Calendar Days Bid  Bidder shall state the consecutive calendar days required to complete all work following a notice to proceed.  (Required: Numbers only)
4	Exceptions  Do you take exceptions to the specifications. If so, by separate attachment, please state your exceptions.  Yes No (Required: Check only one)
5	Insurance
	I understand that the insurance requirements of this solicitation are required and a certificate of insurance shall be submitted to the Purchasing department if I am awarded all or a portion of the resulting contract.  Please initial.
	(Required: Maximum 1000 characters allowed)

Page 4 of 12 pages Deadline: 2/14/2019 02:00 PM (CT) 2019-032 Addendum 3

6	Subcontractors
	State the business name of all subcontractors and the type of work they will be performing under this contract.
	If you are fully qualified to self-perform the entire contract, please respond with "Not Applicable-Self Perform".
	(Required: Maximum 4000 characters allowed)
7	Reference No. 1
	List a company or governmental agency where these same/like products /services, as stated herein, have been provided. Texas references preferred.
	Include the following: Company/Entity, Contact, Address, City/State/Zip, Phone, and E-Mail.
	(Required: Maximum 4000 characters allowed)
8	Reference No. 2
	List a company or governmental agency where these same/like products /services, as stated herein, have been provided. Texas references preferred.
	Include the following: Company/Entity, Contact, Address, City/State/Zip, Phone, and E-Mail.
	(Required: Maximum 4000 characters allowed)

Page 5 of 12 pages Deadline: 2/14/2019 02:00 PM (CT) 2019-032 Addendum 3

9	Reference No. 3
	List a company or governmental agency where these same/like products /services, as stated herein, have been provided. Texas references preferred.
	Include the following: Company/Entity, Contact, Address, City/State/Zip, Phone, and E-Mail.
	(Required: Maximum 4000 characters allowed)
1	Preferential Treatment
0	The County of Collin, as a governmental agency of the State of Texas, may not award a contract to a nonresident bidder unless the nonresident's bid is lower than the lowest bid submitted by a responsible Texas resident bidder by the same amount that a Texas resident bidder would be required to underbid a nonresident bidder to obtain a comparable contract in the state in which the nonresident's principal place of business is located (Government Code, Title 10, V.T.C.A., Chapter 2252, Subchapter A).
	1. Is your principal place of business in the State of Texas?
	2. If your principal place of business is not in Texas, in which State is your principal place of business?
	3. If your principal place of business is not in Texas, does your state favor resident bidders (bidders in your state) by some dollar increment or percentage?
	4. If your state favors resident bidders, state by what dollar amount or percentage.
	(Required: Maximum 4000 characters allowed)
1	Debarment Certification
•	I certify that neither my company nor an owner or principal of my company has been debarred, suspended or otherwise made ineligible for participation in Federal Assistance programs under Executive Order 12549, "Debarment and Suspension," as described in the Federal Register and Rules and Regulations.
	Please initial.
	(Required: Maximum 1000 characters allowed)

2	Immigration and Reform Act  I declare and affirm that my company is in compliance with the Immigration and Reform Act of 1986 and all
	employees are legally eligible to work in the United States of America.
	I further understand and acknowledge that any non-compliance with the Immigration and Reform Act of 1986 at any time during the term of this contract will render the contract voidable by Collin County.
	Please initial.
	(Required: Maximum 1000 characters allowed)
	Disclosure of Certain Relationships
	Chapter 176 of the Texas Local Government Code requires that any vendor considering doing business with a local government entity disclose the vendor's affiliation or business relationship that might cause a conflict of interest with a local government entity. Subchapter 6 of the code requires a vendor to file a conflict of interest questionnaire (CIQ) if a conflict exists. By law this questionnaire must be filed with the records administrator of Collin County no later than the 7th business day after the date the vendor becomes aware of an event that requires the statement to be filed. A vendor commits an offense if the vendor knowingly violates the code. An offense under this section is a misdemeanor.
	By submitting a response to this request, the vendor represents that it is in compliance with the requirements of Chapter 176 of the Texas Local Government Code.
	Please send completed forms to the Collin County County Clerk's Office located at 2300 Bloomdale Rd., Suite 2104, McKinney, TX 75071.
	Please initial.
	(Required: Maximum 1000 characters allowed)
	Anti-Collusion Statement
	Bidder certifies that its Bid/Proposal is made without prior understanding, agreement, or connection with any corporation, firm, or person submitting a Bid/Proposal for the same materials, services, supplies, or equipment and is in all respects fair and without collusion or fraud.
	No premiums, rebates or gratuities permitted; either with, prior to, or after any delivery of material or provision of services. Any such violation may result in Agreement cancellation, return of materials or discontinuation of services and the possible removal from bidders list.
	Please initial.
	(Required: Maximum 1000 characters allowed)

15	Disclosure of Interested Parties  Section 2252.908 of the Texas Government Code requires a business entity entering into certain contracts with a governmental entity to file with the governmental entity a disclosure of interested parties at the time the business entity submits the signed contract to the governmental entity. Section 2252.908 requires the disclosure form (Form 1295) to be signed by the authorized agent of the contracting business entity, acknowledging that the disclosure is made under oath and under penalty of perjury. Section 2252.908 applies only to a contract that requires an action or vote by the governing body of the governmental entity before the contract may be signed or has a value of at least \$1 million. Section 2252.908 provides definitions of certain terms occurring in the section.  Section 2252.908 applies only to a contract entered into on or after January 1, 2016.  Please initial.  (Required: Maximum 1000 characters allowed)
	(Noganiod: Maximum 1000 charactore anomoly)
16	Notification Survey In order to better serve our offerors, the Collin County Purchasing Department is conducting the following survey. We appreciate your time and effort expended to submit your bid. Should you have any questions or require more information please call (972) 548-4165.  How did you receive notice of this request?  Plano Star Courier Plan Room Collin County eBid Notification Collin County Website  Other  (Required: Check only one)
17	Bid Bond Acknowledgement  Accompanying this bid, is a certified check, cashier's check or Bid Bond in the amount of five percent (5%) of the total amount bid. Also accompanying this bid, all the information required in Section 00200 – Instructions to Bidders.  Please initial.
	(Required: Maximum 4000 characters allowed)

Page 8 of 12 pages Deadline: 2/14/2019 02:00 PM (CT) 2019-032 Addendum 3

1	Construction Acknowledgement				
8	Bidder, declares that the only person or parties interested in this bid are those principals named herein, that his/her bid is made without collusion with any other person, firm or corporation, that he/she has carefully examined the Contract Documents including the Advertisement for Bids, Instruction to Bidders, Construction Agreement, Specifications and the Drawings, therein referred to and has carefully examined the locations, conditions and classes of materials for the proposed work, and agrees that he/she will provide all the necessary labor, machinery, tools, equipment, apparatus and other items incidental to construction and will do all the work and furnish all the materials called for in the Contract Documents in the manner prescribed therein.				
	Bidder hereby declares that he/she has visited the site of the Work and has carefully examined the Contract Documents pertaining to the Work covered by the above Bid, and he/she further agrees to commence work within ten (10) consecutive calendar days after date of written Notice to Proceed and to substantially complete the work on which he/she has bid within the number of days specified subject to such extensions of time allowed by Specifications.				
	Bidder certifies that the bid prices contained in this bid have been carefully checked and are submitted as correct and final. The prices have been shown in words and figures for each item listed in this bid and it is understood that in the event of a discrepancy, the words shall govern.				
	Please initial.				
	(Required: Maximum 1000 characters allowed)				
1	Addendum No. 1 Acknowledgement				
9	Please initial to verify your receipt of the addendum.				
	(Required: Maximum 1000 characters allowed)				
2	(Required: Maximum 1000 characters allowed)				
2	Addendum No. 2 Acknowledgement				
2					
2	Addendum No. 2 Acknowledgement				
200	Addendum No. 2 Acknowledgement				
2 0 2	Addendum No. 2 Acknowledgement  Please initial to verify your receipt of the addendum.				
2 0 2 1	Addendum No. 2 Acknowledgement  Please initial to verify your receipt of the addendum.  (Required: Maximum 1000 characters allowed)				
2 0 2 1	Addendum No. 2 Acknowledgement Please initial to verify your receipt of the addendum.  (Required: Maximum 1000 characters allowed)  Addendum No. 3 Acknowledgement				
200	Addendum No. 2 Acknowledgement Please initial to verify your receipt of the addendum.  (Required: Maximum 1000 characters allowed)  Addendum No. 3 Acknowledgement				

## **Bid Lines**

Page 9 of 12 pages Deadline: 2/14/2019 02:00 PM (CT) 2019-032 Addendum 3

	e Bid Grand ponse required							
	antity: <u>1</u>		p sum	Price: \$	Total: \$			
	plier Notes:				Alternate specification (Attach separate sheet)  Additional notes (Attach separate sheet)			
Iten	n Attribute	es						
1. B	. Base Bid Grand Total- Written in Words							
Т	he contract	award will	be based on the to	otal bid price.				
_								
_								
_								
	Dogwirod: Movi	mum 4000 aha	arostoro allowed)					
	•		nracters allowed)	roioat				
_		iai Cost iii	corporated in Pr _	oject				
9								
	Required: Num							
3. T	otal Mater	ial Cost In	corporated in Pr	oject- Written in Words				
_								
_								
_								
_								
<u>/F</u>	Required: Maxi	mum 4000 cha	aracters allowed)					
,	•		prporated in Proj	ect				
_								
(		h h -)						
	Required: Num			and Maritton in Manual				
5. I	otal Labor	Cost inco	rporated in Proje	ect- Written in Words				
_								
_								
_								
(F	Required: Maxi	mum 4000 cha	aracters allowed)					

2	Bid Allowance: Material allowance for networking hardware.								
	Quantity: 1	UOM: lump sum	Total: \$65,000.00						
		The allowance is for material only. Refer to Section 01 21 00, 3.03 and Drawing LV2.	Additional notes (Attach separate sheet)						
	Supplier Notes:								
			_						

Page 11 of 12 pages Deadline: 2/14/2019 02:00 PM (CT) 2019-032 Addendum 3

Supplier intol	mation	
Company Name:		
Contact Name:		
Address:		
Phone:		
Fax:		
Email:		
Supplier Note	)S	
the duly authorized Bidder affirms that t individual has not p line of business; an	agent of said company and the person sig they are duly authorized to execute this con prepared this bid in collusion with any other and that the contents of this bid as to prices, the undersigned nor by any employee or ag	by the company listed below hereinafter called "bidder" is ining said bid has been duly authorized to execute same. ntract; this company; corporation, firm, partnership or bidder or other person or persons engaged in the same terms and conditions of said bid have not been gent to any other person engaged in this type of business
Print Name		Signature