

EXHIBIT "A"
CONTRACT AMENDMENT #2 TO SCOPE OF SERVICES.

PARK BOULEVARD EXTENSION
(CONTRACT NO. 2019-055)

Section B. TASK DESCRIPTIONS – SCOPE OF SERVICES is revised to include the following modifications.

I. Preliminary Engineering

Section A. Data Collection, Item 1. Subsurface Utility Engineering is modified to include:

- e. NTMWD pipeline evaluation: Halff will collect available pipe manufacturer data for lines crossed on grade by the project and prepare detailed load calculations for review by NTMWD. Documents prepared shall include detailed cross section views on each line with proposed paving and minimum/maximum cover depths based on record drawing information and Level A SUE data collected on each line.

Section D. Preliminary Engineering Design is modified to include:

- 7. Prepare design coordination drawings for KCS design approval to include plan profile drawings of the railroad tracks crossed for 1,000 linear feet in each direction from the proposed bridge crossing. Items to be shown shall include existing signals, buried signal lines, switch points, mileposts and other data as required by KCS. Separate drawings shall be prepared for main line tracks as well as the classification yard and intermodal facility tracks. Halff will prepare a separate bridge crossing submittal plan set for KCS coordination and to facilitate proposed crossing agreement approval.

II. Final Engineering

Section A. Final Engineering Design is modified to include:

- 6. Prepare plan/profile designs for Wylie owned water and sanitary sewer lines impacted by the proposed KCS bridge and/or wall construction elements of the project. Prepare special details as required to maintain existing KCS utility services.

IV. Special Services

Section B. Right-of-Way / Easement Documents, Item 3. is revised to increase the number of parent tracts to be solved to approximately 40 parent tracts and the number of separate ROW and/or easement parcel documents to prepare is increased to approximately 75.

Section B. Right-of-Way / Easement Documents, Item 6. Is added as follows:

6. Prepare consolidated ROW strip map exhibits for the project corridor and update as required for coordination purposes with property owners. Prepare separate property coordination maps for parcel identification on KCS owned property.