



COLLIN COUNTY

Office of the Purchasing Agent
2300 Bloomdale Road
Suite 3160
McKinney, Texas 75071
www.collincountytx.gov

ADDENDUM NO. Three (3)

IFB 2021-084

INVITATION FOR BID

FOR

CONSTRUCTION, ROAD: COUNTY ROAD 317 (ORR RD) FROM STACY RD TO SOUTH NTMWD DRIVE

Date: January 19, 2021

NOTICE TO ALL PROSPECTIVE BIDDERS:

PLEASE MAKE THE FOLLOWING CHANGES TO THE INVITATION FOR BID:

DELETE: ADDENDUM No. 2 REVISED Base Bid Schedule (Excel format)
REPLACE WITH: ADDENDUM No. 3 REVISED Base Bid Schedule (Excel format)

- The writing out in words of Dollars and Cents for the Unit Pricing on this form (base bid schedule) has been removed

ADD ATTRIBUTE: #22 - ADDENDUM 3 ACKNOWLEDGEMENT

PLEASE NOTE ALL OTHER TERMS, CONDITIONS, SPECIFICATIONS, DRAWINGS, ETC. REMAIN UNCHANGED.

SINCERELY,
MICHELLE CHARNOSKI, CPPB
PURCHASING AGENT

BID PROPOSAL FOR CONSTRUCTION
CR 317 (Orr Rd) from Stacy Rd to south NTMWD Driveway

BID ITEM NO.	SPEC. ITEM NO.	QTY.	UNIT	BID ITEM DESCRIPTION	UNIT PRICE BID IN NUMBERS	AMOUNT BID
1	500	1	LS	MOBILIZATION	\$ _____	\$ 0.00
2	100	4	AC	ROW PREP	\$ _____	\$ 0.00
3	110	700	CY	UNCLASSIFIED CHANNEL EXCAVATION	\$ _____	\$ 0.00
4	110	2781	CY	UNCLASSIFIED ROADWAY EXCAVATION	\$ _____	\$ 0.00
5	560	6	EA	REMOVE AND REPLACE MAILBOXES	\$ _____	\$ 0.00
6	644	11	EA	REMOVE AND REPLACE STREET SIGNS	\$ _____	\$ 0.00
7	550 & 552	500	LF	REMOVE AND REPLACE FENCE	\$ _____	\$ 0.00
8	360	10812	SY	CONCRETE PAVEMENT (10")	\$ _____	\$ 0.00
9	360	139	SY	CONSTR 10" CONCRETE DRIVEWAY	\$ _____	\$ 0.00
10	360	389	SY	CONSTR 6" CONCRETE DRIVEWAY	\$ _____	\$ 0.00
11	105	10204	SY	REMOVE TREATED AND UNTREATED ASPHALT AND BASE MATERIAL	\$ _____	\$ 0.00
12	340	102	SY	DENSE-GRADED HOT-MIX ASPHALT (SMALL QUANTITY)	\$ _____	\$ 0.00
13	100	2	EA	REMOVE CONC HEADWALL	\$ _____	\$ 0.00
14	100	50	LF	REMOVE STRUCTURE, PIPE (84" STEEL)	\$ _____	\$ 0.00
15	100	72	LF	REMOVE STRUCTURE, PIPE (24" CMP)	\$ _____	\$ 0.00
16	100	50	LF	REMOVE STRUCTURE, PIPE (42" CMP)	\$ _____	\$ 0.00
17	100	242	LF	REMOVE DRWY CULVERT (PIPE)	\$ _____	\$ 0.00
18	460	80	LF	INSTALL 42" CMP (GALV STL) (POLYMER COATED)	\$ _____	\$ 0.00
19	460	48	LF	INSTALL 84" CMP (GALV STL) (POLYMER COATED)	\$ _____	\$ 0.00
20	460	96	LF	INSTALL 24" CMP (GALV STL) (POLYMER COATED)	\$ _____	\$ 0.00
21	464	252	LF	INSTALL 18" RCP (CLASS IV) (DRIVEWAY)	\$ _____	\$ 0.00
22	464	65	LF	INSTALL 24" RCP (CLASS IV) (DRIVEWAY)	\$ _____	\$ 0.00
23	467	16	EA	18" PSET-SP CONC HEADWALL (TY II) (RCP) (6:1)	\$ _____	\$ 0.00
24	467	4	EA	24" PSET-SP CONC HEADWALL (TY II) (RCP) (6:1)	\$ _____	\$ 0.00
25	466	1	EA	42" CONCRETE HEADWALL CH-FW-0 (2:1)	\$ _____	\$ 0.00
26	466	2	EA	24" CONCRETE HEADWALL CH-FW-15 (3:1)	\$ _____	\$ 0.00
27	466	2	EA	84" CONCRETE HEADWALL CH-FW-0 (3:1)	\$ _____	\$ 0.00
28	432	25	SY	CONCRETE RIP RAP (5IN)	\$ _____	\$ 0.00
29	432	212	SY	STONE RIP RAP (COMMON) (18") (DRY)	\$ _____	\$ 0.00

BID PROPOSAL FOR CONSTRUCTION
 CR 317 (Orr Rd) from Stacy Rd to south NTMWD Driveway

BID ITEM NO.	SPEC. ITEM NO.	QTY.	UNIT	BID ITEM DESCRIPTION	UNIT PRICE BID IN NUMBERS	AMOUNT BID
30	100	1	EA	REMOVE INLET	\$	\$ 0.00
31	DRAWING	1	EA	48" CMP DROP INLET	\$	\$ 0.00
32	132	500	CY	EMBANKMENT (FINAL) (DENS CONT) (TY B)	\$	\$ 0.00
33	341	2573	TON	4" HMAC TYPE "B" BASE COURSE	\$	\$ 0.00
34	210	11696	SY	SUBGRADE PREPARATION (6" MOISTURE CONDITION & COMPACTION)	\$	\$ 0.00
35	401	70	CY	FLOWABLE FILL	\$	\$ 0.00
36	666	8030	LF	REF PAV MRK TY II (Y) 4" (SLD)	\$	\$ 0.00
37	666	8030	LF	REF PAVE MRK TY II (W) 4" (SLD)	\$	\$ 0.00
38	164	19320	SY	STRAW/HAY MULCH SEEDING (PERM) (URBAN)(CLAY)	\$	\$ 0.00
39	DRAWING	1	LS	EROSION CONTROL	\$	\$ 0.00
40	502	8	MO	BARRICADES, SIGNS & TRAFFIC HANDLING	\$	\$ 0.00
41	540	100	LF	METAL BEAM GUARD FENCE (MBGF)	\$	\$ 0.00
42	544	4	EA	SINGLE GUARDRAIL TERMINAL (SGT)	\$	\$ 0.00
43	402	130	LF	TRENCH EXCAVATION PROTECTION	\$	\$ 0.00
44	DRAWING	2	EA	PROJECT SIGN	\$	\$ 0.00
TOTAL BID						\$ 0.00