

IFB 2021-315 Culverts, Bands, Drop Structures

				Contech Engineered Solutions LLC	
				Total Price	\$2,409,888.82
Line #	Description	QTY	UOM	Unit	Extended
1	Circular Culverts 12" -- 2 2/3" x 1/2" - 16 gauge	9000	linear foot	<u>\$25.00</u>	\$225,000.00
2	One piece annular band(s) for Circular Culvert 12" - 2 2/3" x 1/2" - 16 gauge	1	each	<u>\$75.00</u>	\$75.00
3	Circular Culverts 15" - 2 2/3" x 1/2" - 16 gauge	10000	linear foot	<u>\$30.00</u>	\$300,000.00
4	One piece annular band(s) for Circular Culvert 15" - 2 2/3" x 1/2" - 16 gauge	1	each	<u>\$90.00</u>	\$90.00
5	Circular Culverts 18" -- 2 2/3" x 1/2" - 16 gauge	6000	linear foot	<u>\$37.50</u>	\$225,000.00
6	One piece annular band(s) for Circular Culverts 18" - 2 2/3" x 1/2" - 16 gauge	1	each	<u>\$112.50</u>	\$112.50
7	Circular Culverts 24" - 2 2/3" x 1/2" - 16 gauge	3600	linear foot	<u>\$47.50</u>	\$171,000.00
8	One piece annular band(s) for Circular Culverts 24" - 2 2/3" x 1/2" - 16 gauge	1	each	<u>\$142.50</u>	\$142.50
9	Circular Culverts 30" - 2 2/3" x 1/2" - 16 gauge	1000	linear foot	<u>\$60.00</u>	\$60,000.00
10	One piece annular band(s) for Circular Culvert 30" - 2 2/3" x 1/2" - 16 gauge	1	each	<u>\$180.00</u>	\$180.00
11	Circular Culverts 36" - 2 2/3" x 1/2" - 16 gauge	1600	linear foot	<u>\$72.50</u>	\$116,000.00
12	One piece annular band(s) for Circular Culverts 36" - 2 2/3" x 1/2" - 16 gauge	1	each	<u>\$217.50</u>	\$217.50
13	Circular Culverts 42" - 2 2/3" x 1/2" - 16 gauge	500	linear foot	<u>\$85.00</u>	\$42,500.00
14	One piece annular band(s) for Circular Culverts 42" - 2 2/3" x 1/2" - 16 gauge	1	each	<u>\$255.00</u>	\$255.00
15	Circular Culverts 48" - 3" x 1" - 16 gauge	600	linear foot	<u>\$110.00</u>	\$66,000.00
16	Two piece riveted annular band(s) for Circular Culverts 48" - 3" x 1" - 16 gauge	1	each	<u>\$330.00</u>	\$330.00
17	Circular Culverts 54" - 3" x 1" - 14 gauge	600	linear foot	<u>\$152.50</u>	\$91,500.00
18	Two piece riveted annular band(s) for Circular Culverts 54" - 3" x 1" - 14 gauge	1	each	<u>\$457.50</u>	\$457.50
19	Circular Culverts 60" - 3" x 1" - 14 gauge	1000	linear foot	<u>\$167.50</u>	\$167,500.00
20	Two piece riveted annular bands) for Circular Culverts 60" - 3" x 1" - 14 gauge	1	each	<u>\$502.50</u>	\$502.50
21	Circular Culverts 72" - 3" x 1" - 14 gauge	2000	linear foot	<u>\$202.50</u>	\$405,000.00
22	Two piece riveted annular band(s) for Circular Culverts 72" - 3" x 1" - 14 gauge	1	each	<u>\$607.50</u>	\$607.50
23	Circular Culverts 84" - 3" x 1" - 14 gauge	600	linear foot	<u>\$235.00</u>	\$141,000.00
24	Two piece riveted annular band(s) for Circular Culverts 84" - 3" x 1" - 14 gauge	1	each	<u>\$705.00</u>	\$705.00
25	Circular Culverts 96" - 3" x 1" - 14 gauge	800	linear foot	<u>\$267.50</u>	\$214,000.00
26	Two piece riveted annular band(s) for Circular Culverts 96" - 3" x 1" - 14 gauge	1	each	<u>\$802.50</u>	\$802.50
27	Circular Culverts 108" - 3" x 1" - 12 gauge	50	linear foot	<u>\$412.50</u>	\$20,625.00
28	Two piece riveted annular band(s) for Circular Culverts 108" - 3" x 1" - 12 gauge	1	each	<u>\$1,237.50</u>	\$1,237.50
29	Circular Culverts 120" - 3" x 1" - 12 gauge	300	linear foot	<u>\$457.50</u>	\$137,250.00
30	Two piece riveted annular bands for Circular Culverts 120" - 3" x 1" - 12 gauge	1	each	<u>\$1,372.50</u>	\$1,372.50
31	Circular Culverts 120" diameter riveted band 24" wide, 2 pc	1	each	<u>\$1,800.00</u>	\$1,800.00
32	Drop Structure 48" diameter inlet 7' long welded to 90 degree elbow with a 36" diameter outlet 26' long from elbow outlet made with 16 gauge galvanized corrugated metal pipe with 2" wide band.	1	each	<u>\$4,948.12</u>	\$4,948.12
33	Drop Structure 72" x 20' 14 gauge drop structure with stub weld and 72" wide band	1	each	<u>\$7,231.80</u>	\$7,231.80
34	Drop Structure 60" x 48" 14 gauge drop inlet structure with one 2' wide 48" band	1	each	<u>\$5,846.40</u>	\$5,846.40
35	Additional fee if delivery requested sooner than 7 business days	1	lump sum	<u>\$600.00</u>	\$600.00
36	Percentage off any item required by the County which does not appear as an item on this bid and is PICKED UP by the County.	1	each	0.0%	
37	Percentage off any item required by the County which does not appear as an item on this bid and is DELIVERED by the vendor.	1	each	0.0%	

Contech will supply all material on this bid with a 3 week leadtime and this will result in Collin County NOT incurring any freight charges. Should a shorter leadtime be required/requested by the County - Freight will apply, and leadtime will be subject to availability of material.