

## Proposal Overview

- Benefits/Scope of Work:** Furnish and install (2) new wall mounted Honeywell thermostats, model # TC500A-N, which offers 4-stages of cooling control and 2 stages of heating control. The existing thermostats are only 2-stage cooling and 2-stage heating.
- Replace existing control wire from thermostats to RTU units using 10 conductor thermostat wire.
- Furnish and install (2) new gas regulators to deliver less than 10 psi incoming gas pressure. The new regulators will be model #Maxitrol 2 PSI Cert. 1-1/2 In. NPT 1-1/4M BTU/H Regulator with 12A49 Vent Limiter including Maxitrol Vent Protector 1/2 In. NPT for 325-7AL. Gas pressure is not currently regulated.
- Exclusions:**
- 1.Labor or material not specifically described above is excluded from this proposal.
  - 2.Unless otherwise stated, any and all overtime labor is excluded from this proposal.
  - 3.Applicable taxes or special freight charges are excluded from this proposal
- Cost Breakdown:**
- |                                |            |
|--------------------------------|------------|
| Honeywell thermostats          | \$1,984.00 |
| Gas regulators                 | \$1,456.00 |
| Thermostat installation/wiring | \$2,450.00 |
| Installation of gas regulators | \$1,200.00 |
| Truck expense                  | \$ 200.00  |
- This quotation is in accordance with Sourcewell contract #070121-JHN.