



January 25th, 2024

Collin County
2300 Bloomdale Road Suite 3160
McKinney, Texas 75071

Attention: David Dooley

Reference: Relocation at Collin County Courthouse

The relocation at Collin County Courthouse scope of work is as follows:

- Locate the existing Collin County Communications Ground Box West of the proposed facility.
- Install 127+/- LF of 2-1.5IN HDPE SDR11 Conduit(s) from existing Collin County Communications Ground Box South.
- Install Collin County Communications Ground Box 127 +/- LF South of existing Collin County Communications Ground Box, sweep proposed conduit(s) inside.
- Install 275+/- LF of 2-1.5IN HDPE SDR11 Conduit(s) from proposed Collin County Communications Ground Box going East. CONDUIT(s) WILL MAINTAIN 8FT DEPTH FROM EXISTING GRADE AT PROPOSED AND EXISTING UTILITIES.
- Install Collin County Communications Ground Box 20 +/- LF North of existing vault, sweep proposed and existing conduit(s) inside.
- Install 402 +/- LF of new 144CT Collin County Fiber cable
- Splice all strands of new 144CT Collin County Fiber cable into existing Collin County OSP Fiber Network, not in conflict.
- Remove 500 +/- LF of 144CT Collin County Fiber cable in conflict.

The cost of this section will be.....\$ 60,779.15

Pricing assumes that all existing underground sections are usable and without damage. Thank you, and please advise as to how we should proceed.

Kyle F. Capps
President