Proposal

Amundson Plumbing, LLC

801 K Avenue, Suite 9 Plano, Texas 75074

469-969-6436

www.amundsonplumbing.com / amundsonplumbing@gmail.com

June 25, 2024

Reference #:
Due Date:

3037-16921 7/5/2024

Job Name:

Myers Park 7117 CR 166 McKinney, TX 75071

Collin County 2300 Bloomdale Road Suite 3160 McKinney, TX 75071

972-548-4122-SUSAN CONTRACT #4503 2023-158

We Hereby Submit Specifications And Estimates For:

Excavate down N. wall, increase 4" to 8" pvc pipe, fittings. Run down wall across parking lot into creek with riff raff spillway. Includes rock at creek to prevent wash-out, pollards at each core drill.

Work can begin 7/10/24 with approval*

EXCAVATION DESCRIPTION: 457ft. Commercial sewer trench, 2 commercial access, 68ft. commercial sewer trench (backfill with concrete crunch 1/2in-3/4in and haul off dirt), at the end of the trench by the creek, put limestone riff raff

Does not include any unforeseen problems/issues, OT charges

Does not include final landscape, excessive rock, or any unforeseen issues/problems underground

Excavation Supervision-2 guys, 5 days	80.00	79.00	6320.00
Installation-4 guys, 3 days	96.00	79.00	7584.00
Concrete R & R with Core Drill	1.00	7830.00	7830.00
Excavation, Backfill, Riff Raff at creek	1.00	48625.50	48625.50
Truck/Equipment, Glue, ect	1.00	225.00	225.00
8" Sch. 40 Pvc Pipe	500.00	8.50	4250.00
8" DWV 8x4 Wye	6.00	86.40	518.40
8" DWV Coupling	22.00	25.70	565.40
Misc. 4" Pvc Pipe, fittings	1.00	2400.00	2400.00
8" 45 DWV	9.00	56.60	509.40
Misc. 2" Steel pipe, caps for pollards	1.00	275.00	275.00
8" Tee, 90, Wye, c/o adapters	1.00	1400.00	1400.00
Collin Co. Discount	1.00	-7.00 %	-694.27

Proposal

Amundson Plumbing, LLC

801 K Avenue, Suite 9 Plano, Texas 75074

469-969-6436

www.amundsonplumbing.com / amundsonplumbing@gmail.com

June 25, 2024

Reference #: 3037-16921 Due Date: 7/5/2024

Job Name:

Myers Park 7117 CR 166 McKinney, TX 75071

Collin County 2300 Bloomdale Road Suite 3160 McKinney, TX 75071

972-548-4122-SUSAN CONTRACT #4503 2023-158

We Hereby Submit Specifications And Estimates For:

Material	Labor	Equipment	Subtotal	Total
9223.93	70359.50	225.00	79808.43	\$79,808.43

Payment to be made as follows:

HALF DUE ON START, BALANCE ON COMPLETION

All material is guaranteed to be as specified. All work to be completed in a professional manner according to standard practices. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above the estimate. All agreements contingent upon delays beyond our control. This proposal may be withdrawn or price adjusted by us if not accepted by the above due date. Responsible Master Plumber, William Amundson, license #23770. General complaints: Texas State Board of Plumbing Examiners P.O.Box 4200. Austin. Texas 75765. 1-800-845-6584.

Authorized	Acceptance	
Signature	Signature	Date