



December 30, 2025

Mrs. Bridell Miers, PE
Collin County Engineering Department
4690 Community Ave, Suite 200
McKinney, Texas 75071

Project Name: CCOL -3C
Project Number: IFB No. 2023-303
Subject: Change Order #06

Dear Mrs. Miers:

BGE, Inc. recommends the following Change Order #06 modifications for the Collin County Outer Loop Project CCOL-3C. This Change Order is for requested safety modifications to the WBFR/FM543 Intersection, WBFR/US75 approach and replacement MBGF at East Fork Trinity Bridge and associated miscellaneous items. This is a lump sum Change Order.

BID ITEM #	SEQ	DESCRIPTION	UOM	UNIT PRICE	ORIG QTY	REVISED QTY	CO QUANTITY	CO AMOUNT
New Item	06-01	Retroreflective Strips FM543/WBFR	EA	\$26.78	0.00	4.00	4.00	\$ 107.10
New Item	06-02	Flags At Stop Signs FM543/WBFR	EA	\$80.33	0.00	4.00	4.00	\$ 321.30
New Item	06-03	Oversized Signs FM543/WBFR	EA	\$4,337.55	0.00	2.00	2.00	\$ 8,675.10
New Item	06-04	Rumble Strips FM543/WBFR	LF	\$16.33	0.00	320.00	320.00	\$ 5,225.37
New Item	06-05	Add Solar Beacons (Stop Ahead Flashing Yellow)	EA	\$5,247.90	0.00	2.00	2.00	\$ 10,495.80
0658-6100	06-06	Install OM ASSM (OM-2Z)(WFLX)(GND)(BI)	EA	\$58.40	43.00	2.00	45.00	\$ 2628.00
New Item	06-07	RFL PAV MRKR TY I-C (White)	EA	\$38.73	0.00	12.00	12.00	\$ 464.82
New Item	06-08	RFL PAV MRKR TY II-AA (Yellow)	EA	\$84.34	0.00	8.00	8.00	\$ 674.73
New Item	06-09	Replace Signal Ahead Sign US75/WBFR	EA	\$374.94	0.00	1.00	1.00	\$ 374.94

BID ITEM #	SEQ	DESCRIPTION	UOM	UNIT PRICE	ORIG QTY	REVISED QTY	CO QUANTITY	CO AMOUNT
New Item	06-10	Replace Damaged Guardrail	LS	\$8,870.04	0.00	1.00	1.00	\$ 8,870.04

Lump Sum
 SUBTOTAL \$37,837.20

06-01 - Retroreflective Strips FM543/WBFR – These Strips are for Reflective Strips on 48x48 Stop Ahead signposts and 48x48 Stop Signs at FM543/WBFR

06-02 - Flags At Stop Signs FM543/WBFR – These four flags are for the two new Stop Ahead Signs (2 EA per sign).

06-03 - Oversized Signs FM543/WBFR – This item is for two sets of 48”x48” Stop signs w/LED flashing lights & two 48”x48” Stop Ahead signs.

06-04 - Rumble Strips FM543/WBFR – This item is for Rumble Strips on both sides of the FM543/WBFR Intersection.

06-05 - Add Solar Beacons (Stop Ahead Flashing Yellow)- This Item is for adding Solar Beacons to both new Stop Ahead Signs at WBFR/FM543 intersection.

06-06 - Install OM ASSM (OM-2Z)(WFLX)(GND)(BI)- This item is for adding object markers adjacent to the WBFR inlet at Station 4720+85 near US75.

06-07 - RFL PAV MRKR TY I-C (White)- These Pavement markers are for enhancing & delineating the existing striping at the US75/ WBFR intersection.

06-08 - RFL PAV MRKR TY II-AA (Yellow)- These Pavement markers are for enhancing & delineating the existing striping at the US75/ WBFR intersection.

06-09 - Replace Signal Ahead Sign US75/WBFR – This item is for replacing the existing Stop Sign Ahead with a Signal Ahead Sign.

06-10 - Replace Damaged Guardrail – This item is for repairing the damaged guard rail at the West Fork Bridge. This damage occurred on December 5, 2025.

The net increase for this **Safety Enhancement Lump Sum Change Order** to this contract for CCOL-3C Change Order #06 is **\$37,837.20**

If you have any questions, please give me a call.

Sincerely,



Parker Scott Hutchins, PE
 BGE Project Manager

Attachments